

CONSTRUCTION ADDENDUM #2

VILLAGE OF GROTON

MUNICIPAL AND PUBLIC SAFETY BUILDING

308 MAIN STREET
GROTON, NY 13073

BDA Project #18118

MARCH 25, 2019

All bidders submitting proposals for the above project shall take note of the following Clarifications, Changes, Additions, and Deletions to the drawings and specifications that become part of the Contract. Receipt of this Addendum shall be acknowledged on the Bid Form. Drawings and Project Manual dated **FEBRUARY 28, 2019**, entitled "**MUNICIPAL AND PUBLIC SAFETY BUILDING, 308 MAIN STREET, GROTON, NY 13073**" are hereby amended, clarified, and modified as follows:

- 2-S1 REFER TO SPECIFICATION SECTION 32 12 16, ASPHALT PAVING:
- At 2.2, **REVISE** Tack Coat to NYSDOT Item: 407.0102.
 - At 2.4, **ADD** Base Course to be NYSDOT Item: 402.258903.
- 2-D1 REFER TO C-SERIES DRAWINGS:
- **REVISE** Civil Drawings per NYSDOT comments. Revisions are clouded on drawing sheets for reference.
- 2-D2 REFER TO DRAWING A-103 FIRST FLOOR REFLECTED CEILING PLAN:
- At locations where Ceiling Type 2 is indicated provide moisture resistant, cleanable 24" x 24" APC.
 - At Room 120, **ADD** GWB Ceiling (Type 3) at 10'-0" AFF.
 - At Room 152, **ADD** APC-1 Ceiling (Type 1) at 9'-6" AFF.
- 2-D3 REFER TO DRAWING A-601 DOOR AND HARDWARE SCHEDULES:
- At Door and Frame Schedule, **REVISE** Hardware group at Door 148B to Hardware Group 24.
 - At Door and Frame Schedule, **DELETE** note "KEY FOB ACCESS CONTROL" in Comments column at Door 144.
- 2-D4 REFER TO DRAWING A-701 ROOM FINISH SCHEDULE & DETAILS:
- **REVISE** sheet in its entirety.

END OF ADDENDUM #2

